BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK/D/E-PMT/06/2012-13 Dated: 13-12-2013

MODIFIED APPROVED TENDER SCHEDULE –'B'

Item No: 35

Name of Work:-Modified Schedule-B for the work of Construction of RCC drain at Puttenahalli KHB colony in ward No-02 of yelahanka Sub

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culvens water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, slacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	66.00	150.00	Rupees one hundred fifty only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a dislance complete as per	Sqm	66.00	78.00	Rupees seventy eight only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 150kgs, with 40mm and down size graded granite metal coarse aggregates @0.692cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS	Cum	10.02	4290.00	Rupees four thousand two hundred ninety only
4	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplaslasisre @ 3lts conforming to IS9103-1999Refilmmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abulments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification	Cum	31.26	5639.00	Rupees five thousand six hundred thirty nine only

Sl	Description	Unit	Approved Qty	Rate Quoted by Contractor / Aoproved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
5	KSR6 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification	Qunt	22.96	7380.00	Rupees seven thousand three hundred eighty only
6	KSR6 4-6.4 : Providing and removing centering, shuttering, struting, propping etc , and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification	Sqm	204.80	270.00	Rupees two hundred seventy only
7	RCC Precast covering slab for drain (10cm thick) as per Modified estimate rate=1237.90	Sqm	266.50	1237.90	Rupees one thousand two hundred thirty seven and paise ninety only

N. Lokanath, REDDY

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.